

- Provision of storage aluminum racks, aluminum doors, paneling, flooring, paints etc.
- Oxygen and suction system connection with the existing hospital pipeline.
- Provision of furniture including benches, LCD TV, water dispenser of MRI waiting area for 20 peoples.
- Complete electricity works from power station to MRI room including power racks, breakers, Electrical DB, Earthing , room lighting as per requirement of the building, wiring, shouko sockets, on/ff switches and power cable from main transformer / hospital LT panel will be the responsibility of the supplier. ACs as per requirement of MRI room, consultant rooms, reporting room and waiting area.
- The installation will be a turnkey project and required modification in the existing site will be the responsibility of the firm including:
 - Machine Room
 - Equipment Room
 - Control Rooms
 - Change Room
 - Reporting Room
 - Consultant Room with attached washroom x 2
 - Waiting Area along with two washrooms for 20 People.
 - Wall Openings for R.F Cabin Door, R.F Window, Quench Pipe and for Filter Plate Installation.
 - Completely closing of wall Opening Immediately after Entrance of Magnet inside the R.F Cabin (MRI Machine Room).
 - False Ceiling of the (Gypsum & Dampa Type); Including Waiting area, Reception, Control Room, Equipment Room, in the whole Building Area.
- The firm will be responsible for complete interface free installation keeping in view the requirement and recommendation of manufacturers and its surroundings to ensure artifacts examinations/procedures.
- Indicating Marking, Warning and Hazard Signs at Main Entrance, Reception.
- Power Generator capacity 200KVA, including ATS panel, Sound Proof Canopy, Foundation Pads, Earthing and cabling.

- Power Transformer capacity 200KVA, including ATS panel, Foundation Pads, Earthing and cabling (LT & HT maximum upto 100 meter) all are responsibility of bidder.
- Foreign training of two doctors (1 Radiologist & 1 Cardiologist) for one week.
- Foreign training of Bio-Medical Engineer for one week.
- 02 x Technician local training for 02 weeks. The comprehensive training covering operations, calibrations and basic services protocols.
- 02 x Application specialist visit for 02 weeks.